

# FIRE SAFETY INSPECTION REPORT

## Risingtex Fashion Ltd.

ACCORD ID: 23386

Aukpara, Ashulia, Savar, Dhaka  
(GPS: 23.88006, 90.297374 )

Other Factories: None



Inspected By: Safawan Abyaz

Date: 08 January, 2019

## Fire Safety Inspection Report

Risingtex Fashion Ltd.

### Introduction:

Risingtex Fashion Ltd. was surveyed for fire safety on 8 January, 2019 by the Accord Inspection Team. The purpose of the survey was to identify significant fire safety issues and to provide recommendations for remediation based on applicable standards specified by the Accord. The scope of this initial fire safety inspection was limited to the review and identification of major fire safety issues. The inspection did not include identification of minor deficiencies, which will be further addressed as part of follow-up inspections.



## Findings & Recommendations :

Table 1 summarizes the major fire safety issues identified during the inspection. Recommendations have been provided to address each issue.

An implementation schedule shall be developed by the factory to remediate each of the findings. The specific timing of improvements, including any requested extensions due to design / installation constraints, shall be submitted to the Accord for approval.

| Sl No.                                                                              | Category                | Findings                                                                                                                                        | Required Action                                                                                                                                            | Remediation Time Frame |
|-------------------------------------------------------------------------------------|-------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
| F-1                                                                                 | Fire Rated Construction | Rooms used for combustible goods storage are not separated by proper fire rated construction. Location: Bonded Warehouse (Main Production shed) | Separate the storage rooms by minimum 1-hr fire rated construction from any other occupancy. The opening protective shall also be minimum 1-hr fire rated. | Within 3 months        |
|  |                         |                                                                                                                                                 |                                                                                                                                                            |                        |



|                                                                                    |                               |                                                                                                                             |                                                                                                                                                                                                                                                                                                                                               |                 |
|------------------------------------------------------------------------------------|-------------------------------|-----------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|
| F-2                                                                                | Egress Lighting               | Manual on-off switch is provided for emergency lighting & exit signage units.                                               | Remove manual on/off switches from emergency lighting & exit signage units to prevent them from being switched off.                                                                                                                                                                                                                           | Within 1 month  |
|  |                               |                                                                                                                             |                                                                                                                                                                                                                                                                                                                                               |                 |
| F-3                                                                                | Fire Detection & Alarm System | Fire detection & alarm system installation requires detailed review to confirm compliance with NFPA 72 and ACCORD standards | <p>Submit as-built drawings, testing records, equipment certification and other relevant documentation to the ACCORD for verification.</p> <p>Upon approval &amp; installation/modification the owner shall contact the Accord prior to conducting the testing &amp; commissioning verification of the fire detection &amp; alarm system.</p> | Within 3 months |

