

M.N. Dyeing, Printing & Washing Mills Ltd

Baniarchala, Bhabanipur, Gazipur sadar, Gazipur

(24.156644, 90.40876)

24 Sep & 09 Oct 2023



Building Information

1. **2-Storied Utility Building:** The structure is a two storied (G+1) RC building.
2. **3-Storied Fiber & Yarn Dyeing Building:** The structure is a three storied (G+M+2) RC building with mezzanine & shed at roof.
3. **Printing Fabric Store:** The structure is a single storied (G) prefabricated steel shed.
4. **Printing Production Shed:** The structure is a single storied (G) prefabricated steel shed with mezzanine.
5. **6-Storied Printing Building:** The structure is a six storied (G+5) RC building.
6. **Bonded Warehouse:** The structure is a single storied prefabricated steel shed.
7. **3-Storied Car Parking & Dining:** The structure is a three storied (G+2) RC building.
8. **2-Storied Garments Printing Production Shed:** The structure is a two storied prefabricated steel shed.
9. **Garments Printing Sub-Station:** The structure is a single storied steel shed.
10. **Diesel Station:** The structure is a single storied steel shed.
11. **Sludge Storage & Screen Washing Shed:** The structure is a single storied bamboo & brick structure.
12. **Maintenance Workshop:** The structure is a single-storied steel roof truss shed.
13. **CP Room:** The structure is a single-story RC building.
14. **RMS Room:** The structure is a single storied RC building.
15. **Market & Fire Control Room:** The structure is a single-storied lightweight steel roof supported by brick columns; roof slab is supported by RC columns.

Observations

Concrete core layout plan not found on site



Centre for Advisory and Testing Services [CATS-MIST (CE)] Military Institute of Science and Technology

Compressive Strength of Concrete Drilled Cores

CATS Reference	: 00490/Con/35120-123/07/2023	Date	: 05.07.2023
Client	: Build Raw		
Project Name & Address	: 6- Storied Printing Building for M.N. Dyeing Printing & Washing Mills Ltd. Baniarchala, Member Bari, Gazipur, Bangladesh.		
Sample Brought By	: Md. Saddam Hossain	Date of Receiving	: 25.06.2023
Test Method	: ASTM C 42/C 42-M	Date of Test	: 03.07.2023
Type of Sample	: Drilled Core	Sample Condition	: Unsealed
Construction Year	: Not Mentioned	Quantity of Sample	: 04 nos
No of Story	: 06-Storey	Type of Aggregate	: Stone Chips

Sl No.	Sample: ID, Location, Structure Type & Grid	Original Length	Sawed Length	Diameter	Crushing Load	Crushing Strength		Failure Type	Fracture Type
		mm	mm	mm	kN	MPa	psi		
1	(Core-5 (Printing)), Ground Floor Column, Q-12a	175.0	133.0	69.0	122.7	32.8	4760	Combined	Shear
2	Core-6 (Printing)), Ground Floor Column, Q-5a	180.0	132.0	69.0	152.3	40.7	5900	Combined	Cone and Shear
3	Core-7 (Printing)), 1st Floor Column, R-2a	160.0	132.0	69.0	131.4	35.1	5090	Combined	Shear
4	Core-8 (Printing)), 2nd Floor Column, Q-11a	190.0	133.0	69.0	166.4	44.5	6450	Combined	Cone and Shear

REMARKS:

1. Core sample collection and submission, location of the sample and other information are provided by the client, and CATS-MIST has not verified the information. CATS-MIST is only reporting the test results of the sample provided by the client.
2. Please compare the results with your corresponding design values and consult with your design engineer.

Test Supervised By:

Gazi Alhaj Hossain
Lecturer
Dept. of Civil Engineering
MIST, Mirpur Cantt, Dhaka


Countersigned By:

Khorshed Sani Ahmed PhD, PE
Asst. Prof. & Associate Professor
Department of Civil Engineering
MIST, Mirpur Cantonment

Note: The results shown in this test report refer only to the samples tested, unless otherwise stated. It is recommended that samples are to be sent in secured and sealed cover/packet/container under the signature of the competent authority in order to avoid fraudulent fabrication of test results. It is also recommended that all test reports are to be collected by duly authorized person and not by the contractor/supplier himself. This test report can not be reproduced, except in full, without prior written permission of the client.

Web: ce-cats.mist.ac.bd

Provided concrete core test report (Typical)



At the time of inspection several sets of concrete core test report were available for the structures. However, no core test layout plan was found at site. Building engineer is required to produce a core layout and mark all the locations of the

Material Test report not available

2.2 Steel Grade

The building is a steel structure. The strength of the steel has considered being A-572 GRADE 50, i.e. yield strength is 345 MPa (50 ~~ksi~~).

2.4 Summary of Material Assessment


Table 0-1 : Strengths of material for the use in analysis and design review.

Material property	Value
For Steel Design yield strength of structural steel, f_y	345MPa (50,000 psi)
For RCC, Rebar strength, f_y	500MPa (72,500 psi)

Structural steel strength considered 50 ksi and rebar strength considered 72.5 ksi in EA report

In EA report, the strength of structural steel was considered 50 ksi and rebar strength considered 72.5 ksi. But there was no test report available on-site. Building Engineer is required to prepare necessary test reports and revise EA documents accordingly.

**Foundation Adequacy not shown in drawing
(mezzanine portion)**



Foundation Adequacy not shown in drawing (mezzanine portion)

Foundation adequacy and details was not shown in as-built drawing of mezzanine floor. Building Engineer is required to revise the as-built drawing and other documents as per actual site condition.

Apparently non-engineered steel stair



Apparently non-engineered steel stair with inadequate member and connection

The stability system of steel stair and its connections are apparently non-engineered. Also, the member size seems to be inadequate. The building engineer is required to suggest proper alternatives to make the structure adequate and prepare necessary design documents accordingly.


Load plan not posted in Mezzanine Floor



Mezzanine floor having no load plan

During inspection, load plan was not found posted in mezzanine floor, which is required to be prepared in compliance with section 1.9.1.1 (part-6, BNBC). Also post the load

Bracing missing in Mezzanine Floor



Bracing found missing in marked location

During inspection, as-built bracing layout was not matched with on-site condition. Building Engineer is required to revise the as-built drawing as per actual on-site condition.

Corrosion on steel member



Corroded steel member

Corrosion found in steel members at several locations. Building engineer is required to identify all corroded member, remove the corrosion and apply suitable anti-corrosive coating to the affected steel members.

Structural connection between two buildings



Building engineer is required to revised the design report and submit to RSC for review considering connections between two buildings (3-Storeyed fiber & yarn dyeing building and 2-storied utility building).

Significant Vibration



Vibrating machine

Significant amount of vibration was observed on the floor due to operation of machine without any damper. The building engineer is required to suggest installation of proper damping elements.

RCC Column suspectable for trolley Impact



Damage RC Column due to trolley

During inspection, Damage in RC Column was found due to trolley Impact. Building engineer required to provide barrier around the RC column to protect from possible trolley impact.

Water ponding on the roof



Water ponding observed on the roof slab due to poor drainage system. The building engineer is required to develop proper drainage system with adequate sloping on roof.

Additional Crane Loading



Over-head crane was observed during inspection. The building engineer is required to check the structural adequacy due to additional

Inconsistencies in Design Report

Design Report Yarn and Fiber Dyeing with 2-storied Utility M.N Dyeing, Printing & Washing Mills Limited

Structure importance co-efficient, $I = 1.00$ (Standard Occupancy, Table 6.2.23, BNBC 2006)
 Response modification co-efficient, $R = 8.0$ along long-direction (Table 6.2.24, BNBC 2006)
 Site co-efficient, $S_s = 1.5$ (Type 2 soil as per Table 6.2.25, BNBC 2006)
 Time period, $T = C_u(h_u)^{1/3}/4$ (Eq. 2.5.3, BNBC 2006)
 h_u = Height in meters above the base to roof = 21.76 m
 $C_u = 0.073$ (RCC frame, Eq. 2.5.5, BNBC 2006)
 $T = 0.073 \times 21.76^{1/3} / 4 = 0.69$ sec

Direction and Eccentricity

Seismic Zone Factor, Z_s
 (e) Per Code: 0.15
 (f) User Defined: 0.15
 Site Coefficient, S : 1.5
 Importance Factor, I : 1

Time Period
 Method A: $T = 0.74$ sec
 Program Calculated: $T = 0.69$ sec
 User Defined: $T = 0.74$ sec

Factors
 Numerical Coefficient, R_w : 8

Figure 3.3.5.1: Earthquake Load Definition along X-direction

Direction and Eccentricity

Seismic Zone Factor, Z_s
 (e) Per Code: 0.15
 (f) User Defined: 0.15
 Site Coefficient, S : 1.5
 Importance Factor, I : 1

Time Period
 Method A: $T = 0.74$ sec
 Program Calculated: $T = 0.69$ sec
 User Defined: $T = 0.74$ sec

Factors
 Numerical Coefficient, R_w : 8

Figure 3.3.5.2: Earthquake Load Definition along Y-direction

Design Report Yarn and Fiber Dyeing with 2-storied Utility M.N Dyeing, Printing & Washing Mills Limited

5.1.1 PILE CAPACITY CALCULATION

Skin friction for cohesive soil is
 $q_s = \alpha C_d A_s$
 α Undisturbed shear strength = $N/8$ ksf
 A_s Surface area of the pile

Skin friction for cohesionless soil
 $q_s = K_s P_d \tan \delta$
 K_s Earth pressure coefficient (1.0 for loose condition)
 P_d d = depth of pile over which the skin friction is calculated
 δ angle of wall friction = 0.75ϕ
 A_s Surface area of the pile


Base resistance of the pile for cohesionless soil
 $Q_b = A_b P_d (N_q - 1)$
 P_d Effective overburden pressure at pile base level y_d , y = unit weight of soil, d = depth
 N_q Bearing capacity factor (Fig. 7.4, Brezantev's Bearing capacity factor)
 A_b Area of pile section

Table 1: Pile Capacity 14

Boring Depth (ft)	Soil Layer Thickness (ft)	Field SPT	Soil Type	Earth Pressure Coefficient, K_s	Angle of Internal Friction, ϕ	Bearing Capacity Factor, N_q	α	C_d	A_s	P_d	Skin Friction, Q_{s1}	Cum. Skin Friction, Q_{s2}	End Bearing, Q_b	Ultimate Capacity, Q_u , ksp
5	5	0	Sand	0	0	0	0	0	23.33	0.144	0.00	0.00	0.00	0.00
10	5	4	Sand	1	28	13	0	0	23.33	0.431	3.86	3.86	6.00	9.86
15	5	7	Clay	0	0	13	0.5	0.9	23.33	0.719	10.21	14.07	10.00	24.07
20	5	10	Clay	0	0	20	0.5	1.3	23.33	1.006	14.58	28.65	21.53	50.18
25	5	9	Clay	0	0	18	0.5	1.1	23.33	1.294	13.13	41.78	24.91	66.69
30	5	25	Sand	1	34.7	51	0	0	23.33	1.581	18.01	59.79	86.28	146.07
35	5	28	Sand	1	35.6	61	0	0	23.33	1.869	21.93	81.72	121.95	203.68
40	5	9	Clay	0	0	18	0.5	1.1	23.33	2.156	13.13	94.85	41.52	136.37
45	5	14	Clay	0	0	26	0.5	1.8	23.33	2.444	20.42	115.26	67.97	183.24
50	5	24	Sand	1	34.4	48	0	0	23.33	2.731	30.81	146.07	140.26	286.32
55	5	24	Sand	1	34.4	48	0	0	23.33	3.019	34.05	180.12	155.02	335.14
60	5	24	Sand	1	34.4	48	0	0	23.33	3.306	37.29	217.41	169.78	387.19

Table 2: Pile Capacity 14

Boring Depth (ft)	Soil Layer Thickness (ft)	Field SPT	Soil Type	Earth Pressure Coefficient, K_s	Angle of Internal Friction, ϕ	Bearing Capacity Factor, N_q	α	C_d	A_s	P_d	Skin Friction, Q_{s1}	Cum. Skin Friction, Q_{s2}	End Bearing, Q_b	Ultimate Capacity, Q_u , ksp
5	5	0	Sand	0	0	0	0	0	23.33	0.144	0.00	0.00	0.00	0.00
10	5	5	Sand	1	28	13	0	0	23.33	0.431	3.86	3.86	6.00	9.86
15	5	4	Clay	0	0	13	0.5	0.5	23.33	0.719	5.83	9.70	10.00	19.69
20	5	6	Clay	0	0	13	0.5	0.8	23.33	1.006	8.75	18.45	13.99	32.44
25	5	6	Clay	0	0	13	0.5	0.8	23.33	1.294	8.75	27.20	17.99	45.19
30	5	35	Sand	1	37.25	85	0	0	23.33	1.581	19.56	46.76	143.79	190.55
35	5	25	Sand	1	34.7	51	0	0	23.33	1.869	21.29	68.05	101.96	170.01
40	5	23	Sand	1	34.1	44	0	0	23.33	2.156	24.08	92.13	101.50	193.63
45	5	10	Sand	1	30	20	0	0	23.33	2.731	30.50	146.24	128.57	274.81
50	5	23	Sand	1	34.1	44	0	0	23.33	3.019	34.39	180.63	164.71	345.34
55	5	25	Sand	1	34.7	51	0	0	23.33	3.306	39.30	219.93	236.99	456.92
60	5	30	Sand	1	36	67	0	0	23.33	3.306	39.30	219.93	236.99	456.92



Calculation considering Cast-in-situ pile where drawing shows pre-cast pile

Building engineer is required to revised the design report and submit to RSC for review.

Significant Crack on Brick wall



During inspection, significant crack on brick wall was observed. Building engineer is required to repair the crack using suitable methodology.

Long column check need to address



Long Slender column

During inspection, long slender column was observed. Building engineer is required to check the slenderness adequacy of the column and suggest proper remedial actions accordingly.

Long column check need to address



Long Slender column

During inspection, long slender column was observed. Building engineer is required to check the slenderness adequacy of the column and suggest proper remedial actions accordingly.

Water ponding on the roof



Water ponding observed on the roof slab due to poor drainage system. The building engineer is required to develop proper drainage system with adequate sloping on roof.

Lack of anchorage of storage rack



Lack of anchorage of storage rack


During inspection, lack of anchorage of storage racks was found. Building engineer is required to brace/anchor all the non-structural elements.

Water ponding on the roof



Water ponding observed on the roof slab due to poor drainage system. The building engineer is required to develop proper drainage system with adequate

Lack of posting load plan



Printing Building without load plan (Typical)

As per BNBC, every building or structure designed shall have its design documents prepared in accordance with the provision of Section 1.9.1, part-6 of BNBC. The design document shall include a design report, and a set of structural drawings, which shall be prepared in compliance with section 1.9.1.1 and section 1.9.1.2 as per BNBC.

During inspection, floor load plan was not found which is required to be prepared in compliance with section 1.9.1.1 (part-6, BNBC).

Lateral stability need to check in details

1. INTRODUCTION

The 6-Storied printing building for "MN Printing and Washing Mills Limited" located at Baniarchala, Member Bari, Gazipur, Bangladesh has been analyzed & designed. The building is an RCC beam column frame structure. The slab thickness is 6 inches. The beam sizes are 10" x 18", 12" x 24", 10" x 20". The column sizes are 15" x 20", L-20" x 20" x 10", 10" x 30". The foundation is on precast RCC pile (14-inch square). The soil test has been done by **ICON Engineering Services**. This report summarizes all the design, drawings, analysis details and design checking related findings.







Figure 1: 3-D VIEW OF 7-STORIED PRINTING BUILDING FOR "MN PRINTING AND WASHING MILLS LIMITED"

The building is apparently slender (length to width ratio > 7). The building engineer is required to check the lateral stability of the structure as per BNBC in details and suggest proper remedial actions if required.

Inconsistencies in Design Report



Mis-match in location and zone (Z)

Inconsistencies in design report was observed. Building engineer is required to revised the design report as per actual condition and submit to RSC for review.

Tested area not filled with specification



Unfilled tested areas

Tested areas of steel structures were found not-filled during inspection. Building engineer is required to fill all the tested area immediately by suitable method.

Apparently non-engineered structure



Apparently non-engineered structure with inadequate member and connection

The stability system of roof & peripheral walls and their connections are apparently non-engineered. The building engineer is required to suggest proper alternatives to make the structure adequate and prepare necessary design documents accordingly. Otherwise, the factory is required to replace the shed with well-designed structure.

Lack of lateral stability System



Truss along short direction was observed but no bracing or load transfer media was provided along long direction. Building engineer is required to check the lateral stability of the structure.

Water ponding on the slab



Water ponding observed on the slab due to poor drainage system. The building engineer is required to develop proper drainage system with adequate sloping on

Dampness on exterior walls



Dampness on Exterior wall

Dampness was observed at the exterior wall of ETP. The factory is required to seal the source of water and repair the damped area with suitable method.

Poor connection against uplift pressure



Apparently inadequate connections were observed at the lightweight roof of the single storied Sheds. The building engineer to check the connection adequacy of the lightweight roof against the uplift pressure of wind.

Marginally stressed beam

Table 6.2.2.1: Comparison Between Max Rebar Provided and Max Required of
Floor Beams

Beam ID	Top Reinforcement		Comments	Bottom Reinforcement		Comments
	Required	Provided		Required	Provided	
B1-250X450	0.36	1.11	ok	0.42	1.28	ok
B2-300X450	0.84	2.08	ok	0.95	2.44	ok
BX-375X400	0.77	1.87	ok	0.33	1.25	ok
BY-450X400	0.47	1.08	ok	0.16	0.72	ok
FB1-250X525	1.2	1.95	ok	0.79	1.46	ok
FB2-250X525	1.64	1.95	ok	1.03	1.46	ok
FB3-250X525	2.05	1.95	ok	1.35	1.46	ok
FB4-250X525	1.02	1.6	ok	0.63	1.46	ok
FB5-250X525	1.23	1.6	ok	0.88	1.46	ok
FB6-250X525	1.12	1.6	ok	0.67	2.44	ok
FB7-250X525	0.28	0.97	ok	0.55	1.60	ok
SB-300X450	0.22	1.95	ok	0.67	1.46	ok

Therefore, all the beams are adequate.

Marginally stressed beam was observed in the design report. The building engineer is required to check the beam adequacy and revise the report as well as take necessary measures accordingly.

Lack of connection adequacy and lateral stability System




Apparently inadequate member size and connections were observed in the lightweight roof. Building engineer is required to check the connection adequacy and lateral stability system of the structure.

Lack of lateral stability system

Observation: 2-Storied garments printing production shed



No compression member or vertical bracing observed and Strut missing



Strut in drawing

No vertical bracing and compression member was observed in the structure that indicates the lateral load path is not logical in long direction against lateral loading. Also strut members are shown in drawing, but no strut members are found during inspection. Building engineer is required to revise the drawing, design report, check the connection adequacy and lateral stability of


Observation: 2-Storied garments printing production shed

Bolt missing & connection gap

Observation: 2-Storied garments printing production shed



Bolt missing



Connection gap

Bolt missing & connection gap found in several connection joints. Building engineer is required to identify all the locations and install missing bolts & resolve connection gaps

Observation: 2-Storied garments printing production shed

Problems Observed

All structures

Item 01: Concrete core layout plan not found on site

Bonded Warehouse

Item 02: Material Test report not available

Printing Production Shed

Item 03: Foundation Adequacy not shown in drawing (mezzanine portion)

Item 04: Apparently non-engineered steel stair

Item 05: Load plan not posted in Mezzanine Floor

Item 06: Bracing missing in Mezzanine Floor

Diesel Station

Item 07: Corrosion on steel member

3-Storied fiber & yarn dyeing building

Item 08: Structural connection between two buildings

Item 09: Significant Vibration

Item 10: RCC Column susceptible for trolley Impact

Item 11: Water ponding on the roof

Problems Observed

Item 12: Additional Crane Loading

Item 13: Inconsistencies in Design Report

Fiber & yarn dyeing sub-station

Item 14: Significant Crack on Brick wall

Item 15: Long column check need to address

2-Storied utility building

Item 16: Long column check need to address

Item 17: Water ponding on the roof

6-Storied printing building

Item 18: Lack of anchorage of storage rack

Item 19: Water ponding on the roof

Item 20: Lack of posting load plan

Item 21: Lateral stability need to check in details

Printing fabric store

Item 22: Inconsistencies in Design Report

Item 23: Tested area not filled with specification

Problems Observed

Sludge Storage & Screen Washing Shed

Item 24: Apparently non-engineered structure

Maintenance workshop

Item 25: Lack of lateral stability System

ETP

Item 26: Water ponding on the slab

Item 27: Dampness on exterior walls

Market & fire control room

Item 28: Poor connection against uplift pressure

3-Storied car parking & dining

Item 29: Marginally stressed beam

Garments printing sub-station

Item 30: Lack of connection adequacy and lateral stability System

2-Storied garments printing production shed

Item 31: Lack of lateral stability system

Item 32: Bolt missing & connection gap

Priority Actions

Item No.	Observation	Recommended Action Plan	Recommended Timeline
01	Concrete core layout plan not found on site (All structures)	The factory is required to prepare core layout plan.	6-weeks
02	Material Test report not available (Bonded Warehouse)	Building Engineer is required to prepare necessary test reports and revise EA documents accordingly.	6-weeks
03	Material Test report not available (Bonded Warehouse)	Carry out suggested remedial works if required.	6-months
04	Foundation Adequacy not shown in design report (mezzanine portion-Printing Production Shed)	Building engineer is required to revise the as-built drawing and other documents as per the actual site condition.	6-weeks
05	Foundation Adequacy not shown in design report (mezzanine portion-Printing Production Shed)	Incorporate foundation adequacy in the design report.	6-weeks
06	Apparently non-engineered steel stair (Printing Production Shed)	The building engineer is required to suggest proper alternatives to make the structure adequate and prepare necessary design documents accordingly.	6-weeks

Item No.	Observation	Recommended Action Plan	Recommended Timeline
07	Load plan not posted in Mezzanine Floor (Printing Production Shed)	Produce and actively manage a set of floor live load plan for all floors based on column and foundation capacity.	6-weeks
08	Load plan not posted in Mezzanine Floor (Printing Production Shed)	Post load plan to all required locations.	6-months
09	Bracing missing in Mezzanine Floor (Printing Production Shed)	The Building Engineer is required to revise the as-built drawing as per actual on-site condition and check the stability.	6-weeks
10	Bracing missing in Mezzanine Floor (Printing Production Shed)	Carry out suggested remedial works if required.	6-months
11	Corrosion on steel member (Diesel Station)	Building engineer is required to identify all corroded member, remove the corrosion and apply suitable anti-corrosive coating to the affected steel members.	6-weeks

Item No.	Observation	Recommended Action Plan	Recommended Timeline
12	Significant Vibration (3-Storied fiber & yarn dyeing building)	The building engineer is required to suggest the installation of proper damper elements.	6-weeks
13	RCC Column susceptible for trolley Impact (3-Storied fiber & yarn dyeing building)	Building engineer required to provide barrier around the RC column to protect from possible trolley impact.	6-weeks
14	Water ponding on the roof (3-Storied fiber & yarn dyeing building)	The building engineer is required to develop proper drainage system with adequate sloping on roof.	6-weeks
15	Additional Crane Loading (3-Storied fiber & yarn dyeing building)	The building engineer is required to check the structural adequacy due to additional crane loading.	6-weeks
16	Additional Crane Loading (3-Storied fiber & yarn dyeing building)	Carry out suggested remedial works if required.	6-months

Item No.	Observation	Recommended Action Plan	Recommended Timeline
17	Inconsistencies in Design Report (3-Storied fiber & yarn dyeing building)	Building engineer is required to revised the design report and submit to RSC for review.	6-weeks
18	Inconsistencies in Design Report (3-Storied fiber & yarn dyeing building)	Carry out suggested remedial works if required.	6-months
19	Significant Crack on Brick wall (Fiber & yarn dyeing sub-station)	Building engineer is required to repair the crack using suitable methodology.	6-weeks
20	Long column check need to address (Fiber & yarn dyeing sub-station)	Building engineer is required to check the slenderness adequacy of the column and suggest proper remedial actions accordingly.	6-weeks
21	Long column check need to address (Fiber & yarn dyeing sub-station)	Carry out suggested remedial works if required.	6-months

Item No.	Observation	Recommended Action Plan	Recommended Timeline
22	Long column check need to address (2-Storied utility building)	Building engineer is required to check the slenderness adequacy of the column and suggest proper remedial actions accordingly.	6-weeks
23	Long column check need to address (2-Storied utility building)	Carry out suggested remedial works if required.	6-months
24	Water ponding on the roof (2-Storied utility building)	The building engineer is required to develop proper drainage system with adequate sloping on roof.	6-weeks
25	Lack of anchorage of storage rack (6-Storied printing building)	Building engineer is required to brace/anchor all the non-structural elements.	6-weeks
26	Water ponding on the roof (6-Storied printing building)	The building engineer is required to develop proper drainage system with adequate sloping on roof.	6-weeks

Item No.	Observation	Recommended Action Plan	Recommended Timeline
27	Lack of posting load plan (6-Storied printing building)	Produce and actively manage a set of floor live load plan for all floors based on column and foundation capacity.	6-weeks
28	Lack of posting load plan (6-Storied printing building)	Post load plan to all the required locations.	6-months
29	Lateral stability need to check in details (6-Storied printing building)	The building engineer is required to check the lateral stability of the structure as per BNBC in details and suggest proper remedial actions if required.	6-weeks
30	Lateral stability need to check in details (6-Storied printing building)	Carry out suggested remedial works if required.	6-months
31	Inconsistencies in Design Report (Printing fabric store)	Building engineer is required to revised the design report as per actual condition and submit to RSC for review.	6-weeks
32	Inconsistencies in Design Report (Printing fabric store)	Carry out suggested remedial works if required.	6-months

Item No.	Observation	Recommended Action Plan	Recommended Timeline
33	Tested area not filled with specification (Printing fabric store)	Building engineer is required to fill all the tested area immediately by suitable method.	6-weeks
34	Apparently non-engineered structure (Sludge Storage & Screen Washing Shed)	The building engineer is required to suggest proper alternatives to make the structure adequate and prepare necessary design documents accordingly.	6-weeks
35	Apparently non-engineered structure (Sludge Storage & Screen Washing Shed)	Otherwise, remove the non-engineered structure.	6-months
36	Lack of lateral stability System (Maintenance workshop)	Building engineer is required to check the lateral stability of the structure.	6-weeks
37	Lack of lateral stability System (Maintenance workshop)	Carry out suggested remedial works if required.	6-months
38	Water ponding on the slab (ETP)	The building engineer is required to develop proper drainage system with adequate sloping on the slab.	6-weeks

Item No.	Observation	Recommended Action Plan	Recommended Timeline
39	Dampness on exterior walls (ETP)	The building engineer is required to seal the source of water and repair the damped area with suitable method.	6-weeks
40	Poor connection against uplift pressure (Market & fire control room)	The building engineer to check the connection adequacy of the lightweight roof against the uplift pressure of wind.	6-weeks
41	Poor connection against uplift pressure (Market & fire control room)	Carry out suggested remedial works if required.	6-months
42	Marginally stressed beam (3-Storeyed car parking & dining)	The building engineer is required to check the beam adequacy and revise the report as well as take necessary measures accordingly.	6-weeks
43	Marginally stressed beam (3-Storeyed car parking & dining)	Carry out suggested remedial works if required.	6-months
44	Lack of connection adequacy and lateral stability System (Garments printing sub-station)	Building engineer is required to check the connection adequacy and lateral stability system of the structure.	6-weeks

Item No.	Observation	Recommended Action Plan	Recommended Timeline
45	Lack of connection adequacy and lateral stability System (Garments printing sub-station)	Carry out suggested remedial works if required.	6-months
46	Lack of lateral stability system (2-Storeyed garments printing production shed)	Building engineer is required to revise the drawing, design report, check the connection adequacy and lateral stability of the structure.	6-weeks
47	Lack of lateral stability system (2-Storeyed garments printing production shed)	Carry out suggested remedial works if required.	6-months
48	Bolt missing & connection gap (2-Storeyed garments printing production shed)	Building engineer is required to identify all the locations and install missing bolts & resolve connection gaps accordingly.	6-weeks