

FIRE SAFETY INSPECTION REPORT

**SHIN SHIN APPARELS LTD.
DAG # RS 228, JL # 73, GORAT, EAST
NORSHINGAPUR, ZIRABO, SAVAR**

OTHER FACTORIES: NONE



ACCORD
on Fire and Building Safety in Bangladesh

June 11, 2014

SUMMARY

SHIN SHIN Apparels Ltd. was surveyed for fire safety on 6/11/2014 by Hughes Associates, Inc. This summary identifies the major deficiencies that were identified during the inspection.

The purpose of this survey was to identify significant fire safety issues and to provide recommendations for remediation based on applicable standards specified by the Accord. The scope of this initial fire safety inspection was limited to the review and identification of major fire safety issues. The inspection did not include identification of minor deficiencies, which will be further addressed as part of follow-up inspections.

Table 1 summarizes the major fire safety issues identified during the inspection. Recommendations have been provided to address each issue.

An implementation schedule shall be developed by the factory to remediate each of the findings. The specific timing of improvements, including any requested extensions due to design / installation constraints, shall be submitted to the Accord for approval.

Table 1. Findings And Recommendations

No.	Category	Finding	Recommendation	Remediation Timeframe
F-1	Fire Rated Construction	Areas used for combustible storage are not separated by fire-rated construction. These areas were found on the ground east side of the building.	Provide dedicated storage rooms separated by minimum 1-hr fire-rated construction. Where separate storage rooms are not feasible, provide defined storage areas and limit the storage arrangement as follows: - Maximum height of 2.4m and maximum area of 23m² - If sprinkler protected: maximum height of 3.66m and maximum area of 93m² Separate areas of unenclosed combustible storage by a minimum clear distance of 3m.	Within 3 months



F-2	Fire Rated Construction	The exit stairs are not separated from work areas, other spaces on each floor by fire-rated construction.	Provide minimum 1.5-hr fire rated doors and seal all unprotected openings to separate the exit stairs from work areas and other building spaces on all floor levels. Ensure that the fire doors are self-closing and positive latching and that they are provided with fire exit (panic) hardware where serving production floors. If fire doors are required to be held open for functional reasons, provide automatic-closing devices tied to the fire alarm system.	Within 3 months
-----	-------------------------	---	---	-----------------





F-3	Egress	Egress doors / gates with locking features are provided at building exits, exit stairs, along egress routes, exit discharges. These were found on all exits and exit discharges in the facility.	Remove locking features from all egress doors / gates. If locks are required for security reasons, utilize special door locking features complying with NFPA 101.	Immediate
-----	--------	--	---	-----------





F-4	Egress	Exit door serving 50 or more occupants does not swing in the direction of egress travel on the ground floor for the east exit and the north and south exit stairwells on the roof.	Modify the egress door to swing in the direction of egress travel.	Within 3 months
-----	--------	--	--	-----------------





F-5	Egress	The width of egress aisles is less than 36-in at the west exit discharge.	Provide minimum aisle widths of 36-in.	Within 3 months
-----	--------	---	--	-----------------



F-6	Fire Protection	The fire alarm system is antiquated, not a listed system, and does not provide alarm and notification features consistent with acceptable standards.	Replace the fire alarm system with a new, listed addressable fire alarm system in accordance with NFPA 72.	Design within 4 months, install within 9 months
-----	-----------------	--	--	---



F-7	Fire Protection	Inspection, testing, and maintenance of the fire alarm system is not in accordance with NFPA 72.	Inspect, test and maintain the fire alarm system, and keep written records on-site, in accordance with NFPA 72.	Within 3 months
-----	-----------------	--	---	-----------------