

FIRE SAFETY INSPECTION REPORT

NEXUS FASHION LTD

VOGRA, JOYDEBPUR

**OTHER FACTORIES: NEXUS KNITWEAR LTD, NEXUS
SWEATER IND LTD**



ACCORD
on Fire and Building Safety in Bangladesh



April 9, 2014

SUMMARY

Nexus Fashion Ltd was surveyed for fire safety on 4/9/2014 by Hughes Associates, Inc. This summary identifies the major deficiencies that were identified during the inspection.

The purpose of this survey was to identify significant fire safety issues and to provide recommendations for remediation based on applicable standards specified by the Accord. The scope of this initial fire safety inspection was limited to the review and identification of major fire safety issues. The inspection did not include identification of minor deficiencies, which will be further addressed as part of follow-up inspections.

Table 1 summarizes the major fire safety issues identified during the inspection. Recommendations have been provided to address each issue.

An implementation schedule shall be developed by the factory to remediate each of the findings. The specific timing of improvements, including any requested extensions due to design / installation constraints, shall be submitted to the Accord for approval.

Table 1. Findings And Recommendations

No.	Category	Finding	Recommendation	Remediation Timeframe
F-1	Fire Rated Construction	Areas used for combustible storage are not separated by fire- rated construction.	<p>Provide dedicated storage rooms separated by minimum 1-hr fire-rated construction.</p> <p>Where separate storage rooms are not feasible, provide defined storage areas and limit the storage arrangement as follows:</p> <ul style="list-style-type: none"> - Maximum height of 2.4m and maximum area of 23m² - If sprinkler protected: maximum height of 3.66m and maximum area of 93m² <p>Separate areas of unenclosed combustible storage by a minimum clear distance of 3m.</p>	Within 3 months



F-2	Fire Rated Construction	The exit stairs are not separated from work areas, other spaces on each floor by fire-rated construction.	Provide minimum 1.5-hr fire rated doors and seal all unprotected openings to separate the exit stairs from work areas and other building spaces on all floor levels. Ensure that the fire doors are self-closing and positive latching and that they are provided with fire exit (panic) hardware where serving production floors. If fire doors are required to be held open for functional reasons, provide automatic-closing devices tied to the fire alarm system.	Within 3 months
-----	-------------------------	---	---	-----------------



F-3	Fire Rated Construction	Unsealed penetrations and openings are located in exit stair enclosures.	Seal all penetrations and openings in exit stair enclosure walls to maintain the fire separation.	Within 3 months
-----	-------------------------	--	---	-----------------



F-4	Fire Rated Construction	Uncovered discharge path to assembly point, with less than 10 ft. building separation, has unprotected openings at a height of less than 10 ft.	Seal all penetrations and openings to the interior of the building, up to a height of 10 ft., to maintain the fire separation. Alternately, provide 1-hr fire-rated separation up to a height of 10 ft.	Within 3 months
-----	-------------------------	---	---	-----------------



F-5	Egress	Egress doors & gates with locking features are provided at building exits, exit stairs, along egress routes, exit discharge. throughout all floors of the factory. All other gates/doors were open and unlocked during the inspection.	Remove locking features from all egress doors / gates. If locks are required for security reasons, utilize special door locking features complying with NFPA 101.	Immediate
-----	--------	--	--	-----------



F-6	Egress	Collapsible gates & sliding doors are provided at main building exits and along egress routes.	Replace all gates / sliding doors along the means of egress with side-hinged, swinging egress doors. If locks are required for security reasons, utilize special door locking features complying with NFPA 101.	Within 1 month
-----	--------	--	--	----------------



F-7	Egress	The width of egress aisles is less than 36-in on the first floor storage area.	Provide minimum aisle widths of 36-in.	Within 3 months
-----	--------	--	--	-----------------



F-8	Fire Protection	The fire alarm system is antiquated, not a listed system, and does not provide alarm and notification features consistent with acceptable standards.	Replace the fire alarm system with a new, listed addressable fire alarm system in accordance with NFPA 72.	Design within 4 months, install within 9 months
-----	-----------------	--	--	---



F-9	Fire Protection	Inspection, testing, and maintenance for the fire alarm system were not in accordance with NFPA 72.	Inspect, test and maintain the fire alarm system, and keep written records on-site, in accordance with NFPA 72.	Within 3 months
F-10	Fire Protection	The building is equipped with single-station smoke alarms. Smoke alarm activation sounds only a local alarm and does not provide automatic fire alarm notification of occupants.	Remove single-station smoke alarms. Provide automatic smoke detection throughout the building in accordance with NFPA 72.	Within 6 months



F-11	Egress Lighting	Manual on-off switch is provided for emergency lighting / exit signage units on all floors of the factory.	Remove manual on/off switches from emergency lighting / exit signage units to prevent them from being switched off.	Within 1 month
------	-----------------	--	---	----------------



F-12	Egress Lighting	Inspection, testing, and maintenance records for the emergency lighting system were not available.	Inspect, test and maintain the emergency lighting system in accordance with The ACCORD standard. Keep written records on-site.	Within 3 months
------	-----------------	--	--	-----------------