

Hannan Knit & Textiles Ltd.

505, Kalmeshor, Board Bazar, National University, Gazipur-1704, Dhaka
(23.94233E, 90.38211N)
27 April 2014



Building Observations

Fire protection to steelwork



It was not possible to determine if there was fire protection applied to the steelwork.

Fire protection to steelwork

Roof stability system



Roof bracing, which appears to be coated steel cable, was found to be slack at some locations, with purlins acting as compression struts.



Roof stability system

Priority Actions

Problems Observed

1. Fire protection to steelwork
2. Roof stability system

Item No.	Observation	Recommended Action Plan	Recommended Timeline
1	Fire protection to steelwork	Building engineer to review adequacy of fire protection to steelwork	6-weeks
2	Fire protection to steelwork	Any required remediation work to be completed	6-months
3	Roof stability system	Building engineer to review adequacy of roof stability system including cable bracing and compression struts	6-weeks
4	Roof stability system	Any required remediation work to be completed	6-months